Observatory Automation Project Preliminary Design Review Electric Dome Drive System



Steven Bauman

Contributors: Sarah Gajadhar, Grant Matsushige, Ivan Look, Derrick Salmon, Ralph Taroma, Larry Roberts, Casey Elizares, Tyson Arruda, William Cruise, Tom Vermeulen, Jim Thomas, DeeDee Warren, Karun Thanjavur

Version 2.0 April 6, 2010



Scope

- Design solution to operate the Dome system with electronic drive units.
- Control remotely under the guidelines provided by the OAP project
- Outline the requirements for the system, document the existing system, discuss design alternatives, and detail the preliminary system design, interfaces, safety considerations, estimated costs and resources.



Requirements

Dome drive requirements needed for OAP

Remote Dome drive Operation

The Dome drive must be capable of being operated in a "safe" reliable manner from Waimea.

Remote monitoring and status

The electronic drive system shall provide necessary status and system information.

Manual Control

The drive system control panel must allow local control of the drive system.

Preventative Maintenance

 The dome drive system shall provide access to all serviceable components and minimize the need for scheduled maintenance.


Improved Reliability

The new electronic dome drive system should increase the reliability and minimize repairs.

Safe Interlocking

 The dome drive system shall provide safety interlocking to prevent unauthorized remote control of the drive system. It shall protect personal and other critical systems when/if other systems shutdown or malfunction





Pressure Indicator

Temperature Indicator

Switch

Pressure Switch

Current Hydraulic Drive System


- •5th Floor
 - •Three (3) Hydraulic drive units
 - •Hydraulic motors
 - •Drive train (includes gear reduction box)
 - •Hydraulic actuators
 - •Servo valves, pressure switches,

Filters, fittings, lines, etc.

- •1st Floor
 - •Hydraulic power unit
 - •Two (2) 20HP motors
 - •Two (2) HP pumps
 - •Two(2) LP pumps
 - •200 Gallon Reservoir
 - •Filters, pressure switches, check valves, lines and fittings.



Dome Drive Unit Components





Design Alternatives from Feasibility study

Manufacture:

Baldor Technology

Vendor:

Kaman Industries

- Baldor proposes three (3)
 Baldor 22H Line Regen AC
 Motor Control Drive Units
- With three (3) Baldor RPM AC Motors

Manufacture:


Rockwell Allen-Bradley


Vendor:


One Source

- Allen-Bradley proposes three (3) Air-cooled
 PowerFlex 755 Drive Units
- With three (3) Baldor RPM AC Motors

New Motors and Adapter








✓ Meets Preventative Requirement



New Location for Dome Drive cabinet






Dome Drive Motor Controller Cabinet



- •Drive unit enclosure electrical
 - •New fuse disconnect and circuit breaker panel is included with the motor controller enclosure for either manufacture.
 - •Electrical conduit needs to be installed from the fourth floor lama room to the 5th floor visitor's gallery
 - •The DP4 distribution panel in the back of the lama room will be used to power the equipment on the fifth floor.







Parking Brakes (not de-acceleration brakes)

	Pros		Cons	
Option 1	✓ ✓	Uses weather PLC information already established and trusted. Does not require additional equipment to purchase, install, or maintain. Operating duration and wind parameters can be tweaked in PLC code.	0	Excessive use will reduce motor lifetime. Consumes electricity when being used.
Option 2	✓	Simpler installation and maintenance than option 3 or 4.	0	Another electro-mechanical device to maintain. Consumes continuous power during dome movement.
Option 3	√	Could complicate the Motor adapter kit installation	0	May require additional interface modifications to the adapter kit and motor coupling.
Option 4	√		0	May require additional interface modifications to the adapter kit and motor coupling.



7 SO Series Electric Clutch Couplings

- · Couples in-line shafts
- · Zinc chromate plating for corrosion resistance
- . 9 sizes for shaft diameters 3/16" 1"



- · Power-on brake, engages when voltage is applied, releases when voltage is turned off
- . 9 sizes for shaft diameters 3/16" 1"



Spring set friction type brakes

•Option 1: Motor brakes/Clutch

•Option 2: Brake located on the end of

the motor drive shaft

Option 3: Double C-face brake

Option 4: System brake



*7 FSB & FSBR Series Power Off Brakes

- · Flange mounted
- · Engages when voltage is removed
- . 7 sizes for shaft diameters 3/16" 3/4"
- · Non-asbestos, non-lead friction material for long-life and guite
- · Designed for applications requiring minimal space
- . 5 sizes for shaft diameters 5/16" 3/4"
- · Non-asbestos, non-lead friction material for long-life and quiet operation



✓ Meets Safe. interlocking Requirement



Drive Unit Frame Actuator Pivot

☐ Since the actuator depends on the hydraulic system pressure to function a replacement must be installed.


oThe actuator rotates the frame for replacement of the dome wheel and applies additional force to the dome drive wheel on the track.

□ Replacement Actuator options:

- ☐Pneumatic actuator
 - oParker Hannifin
 - **oNumatics**
 - oCylindrix 0


✓ MeetsImprovedMaintainabilityRequirement






Pneumatic Actuator

Solenoid Valve









Heat Mitigation strategy

- Heat dissipation estimates
 - Motors
 - At Full Speed (3.4HP @ 60°/min) ~ 95 Watts
 - Meets requirement criteria
 - Motor Controllers
 - At Full Speed (3.4HP @ 60°/min) ~ 256 Watts
 - Worst case estimate
- Both the motors and motor controllers will be turned on/off and driven intermittently under automatic TCS or manual control.
 - To mitigate heat from the drive enclosure which houses the motor controllers, ducting and a fan could be installed.
 - The proposed location for the drive enclosure is on the 5th floor in the visitors' gallery.
 - The routing for the ducting will run from the top of the enclosure up the wall and terminate on the side wall of the 5th floor visitors staircase

PLC Block Diagram



Modified PLC Interface-Dome drive motion




- •The last module in the PLC rack is a 1746 NIO4V 2ch analog input/voltage output device
- •This device currently outputs the ± 10V signal to the servo amp for the dome control movement.
- •The wiring will interface from the O: 6: O ± pin connecters on the PLC to the J1:4&5 input pin connectors on the motor controllers

✓ Meets Remote Dome Drive Operation Requirement

Dome Drive-Motor Controller enable/disable

- •One output pin connector available on the second module in the PLC rack which is a 1746-OG16, a 16 bit TTL (transistortransistor logic) standard 5v computer interface output module
- •This signal would be used to enable/disable the motor controllers.
- •The wiring will interface from the O: 2/15 would be wired to J1:8 enable/disable pin connectors on the motor controllers







✓ Meets Remote Dome Drive Operation Requirement

Dome Drive Manual control-Via 5th floor



Indicator Lights LCD DISPLAY JOG -Displays control status including LOCAL or REMOTE operation, motor direction Used to call up preprogrammed JOG command, set value of each parameter/function, monitoring values such as output frequency and current, also displays fault conditions and log. **FWD** Used to initiate a PROG forward direction run o Used to access the block the motor. programming area LUP Used to initiate a reverse direction run of Used to change the display parameter or parameter value up one STOP increment. Used to initiate a motor stop command. ENTER Used to take the block SHIFT Used to toggle between Used to move the LOCAL and REMOTE down one level while saving any changes. blinking cursor ove one space for each push of the SHIFT key. DISP **DOWN** Depressing this key changes RESET Used to change the the displayed control status. Also used to bring the lower Used to initiate a logical reset display parameter or parameter value down block programming menu after a fault condition and to back to the monitoring menu.

take the block programming menu up one level.

one increment.


•Local Remote Switch on the 5th floor for selecting the automatic/manual/off configuration of the dome drive

Options

- Remote pendent station (hand held control device) with a cord that plugs into the drive controller
- Bipolar potentiometer speed reference could keep the 5th manual control panel the same
- HIM (human interface module) which can operate the dome drive from the drive cabinet

✓ Meets Manual Control Requirement

Dome Drive Motor Controller Status



- •Third module in the PLC rack is a 1746-IG16, a 16 bit TTL standard 5v computer interface Input module
- •Device currently stores Dome status drive on/off, drive enable/disabled, dome ready
- •The wiring will interface the I:3/10-14 pin connecters of the 1746-IG16, to the outputs J1:19, 20, 21, 22 pin connectors of the motor controllers.

✓ Meets Remote Status Requirement



Dome Drive Monitoring Status Information

Motor Controller

- The motor controllers store valuable data about the functionality and health of the drive system
- With OAP in mind, the chosen system needs to provide this information
- The Outputs can be chosen from a large table with parameters such as; speed, torque, voltage, current, etc

Communication Methods

- Add output module cards to the motor controller unit which will provide 4 analog or digit signals.
 - This will require an empty slot in the PLC chassis for an analog input module card and the card itself.
- Add serial interface communication (RS232) expansion boards to the motor controllers.
 - This would allow use to receive feedback information for status via and RS232 cable to a Pearle device
 - Using the Pearle device we could receive the information via and Ethernet cable and get the various status information we need.

✓ Meets Remote Monitoring Requirement

Motor Sizing Requirement						
Requirement	 Full running speed (60°/min) - power output requirement Full running speed (60°/min) - power output of current speed (60°/min) - power output output power (HP) output power drive wheel 					
Motor inefficiency	The RPM AC motors are 94% efficient, therefore the motor inefficiency that must be accounted for is an additional 6%	 3.4 HP ÷ .94 = 3.6 Hp The addition added to the requirement = 3.6 HP 				
Motor de-rating	 The Baldor RPM AC motors and Line Regen AC flux vector controllers have to be de-rated for 14,000ft elevation operation. The de-rated was calculated to be 32.4% 	 3.6 HP ÷ .676 = 5.35 HP The addition added to the requirement = 5.35 HP 				
Safety Factor	 From the requirements document of the dome drive electric upgrade The safety factor = SF = 2.5-3 	 5.35 HP x 2.5 = 13.4 HP 5.35 HP x 2.5 = 16.05 HP The motors should be sized between 13.4 HP to 16.05 HP per drive wheel (unit) 				
	Reasons for upgrading to a larger motor configuration, 20HP					
Maintenance	A larger motor when compared to a smaller equivalent motor would have a longer run life and require replacement less often					
Drive train capacity	The current drive train (gearbox is the limiting component) is rated to accommodate a 20HP motor					
Heat Production	A larger motor with the same load as a smaller equivalent motor will produce less heat.					
Designing for the future	Future projects may increase the weight of the dome and could affect later performance of the drive system					
Function	If one drive fails, we could still operate at full speed (60°/min) with two drives.					
Reliability	A larger motor when compared to a smaller equivalent will have a longer lifetime at the same duty cycle.					
Cost difference	The cost difference between a 15HP system and a 20HP is minimal.					
Unforeseen advantages	 Larger motors could provide the torque needed to break ice built up on the dome Larger motors could provide the torque needed to battle high winds 					

	Comparison of Baldor vs. Rockwell Allen-Bradley					
	Baldor	Rockwell Allen-Bradley				
Motors	 Almost any motor will work with the proposed system Recommends Baldor motors for driven applications 	 Almost any motor will work with the proposed system Recommends and specifies Baldor motors for driven applications 				
Regenerative	The 22H motor controller is a proven and understood technology, Keck implementation	 The 755 Motor controller is a new line of motor controller products One Source Supplier has little experience with newer technology. 				
Support	 Excellent engineering support from Baldor and Kaman Oahu merchandise supplier for Baldor products is Kaman Industrial Technologies Lower priced of the two for integration and commissioning 	 Excellent track record over the years for support from Allen-Bradley. Oahu merchandise supplier for Rockwell-Allen Bradley products is One Source Berkley Engineering 				
Communication	 Motor controller provides 4 optical (digit) outputs built into the unit. Analog output cards can be added to the motor controller for feedback such as current, voltage, speed, etc. RS232 serial interface using a Pearle device will allow Ethernet communication capabilities for remote status Requires not additional software or processors 	 Motor controller requires a Compactlogix processor to communicate with our SLC 505 This Compactlogix processor requires a software upgrade to RSLogix 5000 The processor allows communication by Ethernet IP cable directly to the SLC 505 Adds another processor to maintain (with a spare) and additional software licenses to purchase and support 				
The 22H motor control is flexible and can be configured for different applications		The 755 motor control is extremely versatile and can be configured for multiple applications				

Time and resource	e estimates	Resource	Days	Description
		SB	1	Order Brevini Motor Adapter kit
			1	Order Spare Motor
		SB, Daycrew	3	Finalize Actuator selection
		SB	1	Order Pneumatic actuators
		SB, Daycrew	1	Order Pneumatic actuator lines, couplings, etc.
		SB, Daycrew	2	Remove the door casting and/or room walls as needed in the detector room.
		SB, Daycrew	3	Run pneumatic lines and fittings to actuators
	Hardware, mechanical	SB, Daycrew	3	Mount and install new Pneumatic Actuators
		SB, Daycrew	1	Test pneumatic actuator function, line pressure, and leak detection
		SB, Daycrew	4	Finalize Anti-rotation (brake) design and materials.
			8	PLC requirements for status and monitoring
		SB,GM		PLC Wiring design (±10V signal, Motor controller enable/disable, Manual Control, Local/Remote, status feedback)
		SB, DS, SG	5	Motor controller requirements and final configuration
		SP CM	10	PLC software upgrade
		SB, GM	5	PLC wiring block diagram
	Software	TV, SB,GM	3	PLC requirements for status monitoring
Post PDR and			2	Overall GUI/status page design
Detailed Design		SB, GM	5	PLC software control code changes
Work			5	PLC software interface changes
		SB, TV, GM	5	Overall interface, control, and display.
		SB,GM	10	Testing with PLC Rack, motor controller and motor communication in Waimea
		SB, Daycrew	2	Layout design for 2 sets of conduit (1/2" and 3/4") for the motor power and feedback cables.
				Layout design for the conduit from the 4th floor to the 5th floor. 460V power
		SB,LR	1	Order Conduit, electrical wiring, other materials.
	Electrical	SB, LR, Daycrew	5	Install 2 sets of conduit (1/2" and 3/4") for the motor power and feedback cables.
				Install the conduit from the 4 th floor to the 5 th floor.
				Pull 1 awg. Electrical wire from the 4 th floor to the 5 th .
				Pull 8 gauge wires for motors, i.e. electrical wire from the drive units to the drive cabinet location.
		SB, GM	4	Create drawing layout of wiring diagrams
		SB, Daycrew, GM	2	Drive unit cabinet wiring layout
		SB, DS, Daycrew	2	Drive unit final specifications approval

	Hardware, mechanical	SB	1	Order Drive unit package-Place P.O.		
			1	Cabinet wiring check. Test wiring continuityTest wiring connections from DP4 distribution panel to 5 th floor.		
	Electrical	LR, SB	1	Motor Wiring Check, Test wiring continuitypower and feedback cable from drive units to motor controller cabinet.		
	Software	SB, GM	5	PLC integration, wiring, and test		
		SB, GM	3	PLC consultation and troubleshooting		
		SB, TV	2	Status/monitoring page test		
		SB, Daycrew	2	Manual/automatic system tests		
		LR, Daycrew, SB	2	Install new drive unit package enclosure (motor controllers)		
		LR	1	Connect 1awg wiring to the drive unit. Test functionality		
	Electrical	LR, SB, Daycrew	1	Finished motor controller package install and checkout.		
		-		Hydraulic motor retrofit work begins a few days before the motor control unit delivery is expected		
				Remove old hydraulic motor and adapter kit from drive unit #2.		
		SB,	2	Rotate Brevini gearbox 90 degrees		
		Daycrew	2	Install new Brevini adapter kit on drive unit #2		
				Install new Electric motor on drive unit # 2		
				Install parking brake/clutch on electric motor (optional-TBD)		
		WC, GM, SB	4	TCS Testing with new electric drive unit #2		
Implementatio		SB, Consultant	1	Motor controller consultant arrives on island		
n		SB,		Dome drive Consultation Commissioning and Testing-Begin day testing of VFD system.		
(Integration)		Daycrew, WC, GM, Consultant	2	Test drive unit # 2 under electric motor control		
	Hardware,			Prefer to perform Unit #3 retrofit when F/8 is on telescope		
	mechanical			Remove old hydraulic motor and adapter kit from drive unit #3		
		SB,	1	Rotate Brevini gearbox 90 degrees		
		Daycrew	'	Install new Brevini adapter kit on drive unit #3		
				Install new Electric motor on drive unit # 3		
				Install parking brake/clutch on electric motor (optional-TBD)		
		SB,		Test drive unit # 2 and 3 under electric motor control.		
		Daycrew, WC, GM, Consultant	2	New electric drive system Commissioned and ready for nightly operations-under two drive unit operations temporarily.		
				Remove old hydraulic motor and adapter kit from drive unit #1		
		SB,		Rotate Brevini gearbox 90 degrees		
		Daycrew	3	Install new Brevini adapter kit on drive unit #1		
				Install new Electric motor on drive unit # 1		
				Install parking brake/clutch on electric motor (optional-TBD)		
	Software, Electrical	SB, GM, WC,	5	Test drive unit # 1, 2 and 3 under electric motor control.		
		Daycrew	3	Phase 1 Finished- Dome drive system now under electric drive system control.		
	Software,	SB, Daycrew	1	Monitor heat dissipation in visitor's gallery.		
	Mechanical	52, 23,01011	1	Install heat mitigation equipment if needed.		
				Phase 1 Complete		
		Subtotal:	44	Days		
Father to 1	Subproject Total: 140 Days –days for Phase 1, ~8-10 months					
Estimated completion date: Oct 2010						

Equipment and Material Costs					
Component description	Allen Bradley	Baldor	Notes		
·			·		
22H Line Regen AC Flux Vector motor controller package drive system. Baldor		\$38,293.00	Includes: Drive system package, includes 3X ZD22H425EL motor controllers and equipment needed to assemble the package, see appendix P for more detail.		
ZD22H425EL motor controller (drive unit) – qty 1 Baldor		\$12,722.46	Special pricing when purchased all at once, otherwise purchased separately \$13413.67		
20 HP RPM AC motors-qty 4 Baldor		\$10,733.96	Special pricing when purchased all at once, \$2683.49 each. Otherwise purchased separately \$5268.27		
Power flex 755 Regenerative AC motor controller package drive unit Rockwell Allen-Bradley	\$52,718.00		Includes: Drive system package, see appendix Q. Includes four (4) motors and four (4) motor controllers. But is not quoted for the correct motors, and does not include some equipment the other quote does. Awaiting new quote which will be more accurate.		
Support Engineer for Commissioning	\$9,751.00	\$5000.00	Plus travel expenses, i.e. airfare, lodging, rental car.		
Electrical wiring upgrades	\$5000.00		New 1awg wiring and conduit run from the 4 th floor to the 5 th floor, 8 gauge wire and conduit for the motor power runs.		
 Drive cabinet enclosure heat mitigation Heat exchanger ~\$400-500 includes dual fan Glycol lines and fittings 	\$1500.00 s dual		Parts and materials needed to duct the heat from the drive enclosure.		
Pneumatic actuators for the dome drive frames Parker Hannifin	\$3,017.52		Includes: four (4) Pneumatic actuators, \$632.68 each; 1 of which is a spare. And four (4) Rod clevis, Pins, etc.		
Pneumatic Solenoid valves, air lines, and fittings	\$3,1	20.00	Includes: four (4) Solenoid valves, lines and fittings.		
Brevini Motor adapter kits-qty 4	\$ 2,5	541.08	Includes 3 motor adapter kits and one spare kit. \$635.27 each.		
Brakes	\$11,000.00		Optional, Includes 3 spring brake sets and one spare. \$2,750.00 each		
Misc materials and supplies	\$750.00				
TOTAL	\$89,397.60	\$93,678.02			
	Allen-Bradley				

Any Additional Questions or Comments?



Thank you for your time!

